ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಟಿಪ್ಪಣಿ ಪಾಳಿ

ಫೈಲ್ ಸಂಖ್ಯೆ.....
ಕಡತದ ಸಂಖ್ಯೆ.....

ನಂಬಿಕೆಯ ಸಂಖ್ಯೆ	ಟಿಪ್ಪಣಿಗಳು ಮತ್ತು ಆಜ್ಞೆಗಳು
	ವಿಷಯ: ವಾರ್ಡ್ ಸಂಖ್ಯೆ: 100ರಲ್ಲಿ ನಾಮ ಫಲಕವನ್ನು ಒದಗಿಸುವ ಕಾಮಗಾರಿಗೆ ಡಾಟಾ ದರವನ್ನು ಅನುಮೋದಿಸುವ ಬಗ್ಗೆ.
	****
	ಮೇಲ್ಕಂಡ ವಿಷಯಕ್ಕೆ ಸಂಬಂಧಿಸಿದಂತೆ, ವಾರ್ಡ್ ಸಂಖ್ಯೆ: 100ರಲ್ಲಿನ ನಾಮ ಫಲಕವನ್ನು
	ಒದಗಿಸುವ ಕಾಮಗಾರಿ ಬಾಬ್ತು 2009-10ನೇ ಸಾಲಿನ ಎಸ್.ಆರ್.ದರ ಪಟ್ಟಿಯಲ್ಲಿ ಇರುವಂತೆ
1	ಸಾಮಗ್ರಿಗಳ ಮೊತ್ತ, ವೆಲ್ಡಿಂಗ್, ಫ್ಯಾಬ್ರಿಕೇಶನ್ ಹಾಗೂ ಬಣ್ಣ ಮತ್ತು ಸ್ಟಿಕರ್ ಕಟ್ಟಿಂಗ್ ಬಾಬ್ತು
	ಎಸ್.ಆರ್. ದರವನ್ನು ಲೆಕ್ಕಾಚಾರ ಮಾಡಿ ವಿವರಗಳನ್ನು ಈ ಕೂಡ ಲಗತ್ತಿಸಲಾಗಿದೆ.
	ಆದುದರಿಂದ ಮೇಲ್ಕಂಡ ನಾಮಫಲಕಕ್ಕೆ ತಗಲುವ ರೂ. 6,20,000/-ನ್ನು ಅನುಮೋದನೆಗಾಗಿ
2	ಮಂಡಿಸಿದೆ. [illegible]
	ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು, ಪೆಬ್ಬಾಳ ವಿಭಾಗ, ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.
3	ಎ.ಪಿ.ಸಿ (ಪೂ) ಮು.ಆ (ಪೂ)

TA
pl verify & put up

BRUHAT BANGALORE MAHANAGARA PALIKE

Detailed Estimate for Providing & Fixing Name Boards in Hebbala Division

Sl. No	Description	Unit	No	Dimensions L	B	D	Qty	Rate	Amount
1	Providing MS pipe name boards made of 3" (75 mm) dia MS pipe for vertical pole and 3 no of horizontal support pipe of 11/2" (38") dia pipe each of length 1.00 mtr signage board of size 60X45cm and 60X23cm size made of 16 gauge MS Sheet welded to MS square tube frame of size 25X25mm all manal are cut size and all item electricals welded as per the drawing all joints are grinded smooth and painted with two coats of approved colour synthetic enamel paint over a coat of industrial prime and painting the required detail in fountain on either side of board as per the details provided etc , complete								
I	Cost of Material								
a)	3" dia MS pipe				4.25 Mtr				
	Cost per mtr				6.44 kg/mtr				
					27.77/kg				
b)	Horizontal MS pipe 1 1/2" dia = 3X1.00=3.00 mtr								
	Weight per mtr 1.98 kg/mtr = 5.94 kgs								
C)	MS Square pipe 25X25mm								
	60X60+45+45+60+60+23+23 -376 = 3.76								
d)	14 gauge MS Sheet								
	2X0.6X0.45 = 0.54 M2								
	2X0.6X0.23 0.27 M2								
	0.81 m2								
	Cost per sq mtr 15.70 kg / mt X 12.71								
	Total Weight 53.86								
	Add 5% Wastage 2.69 (P XIV Sl. No. 383)						56.55	34.98	1978.12
2	Welding charges								300.00
3	Hire charge for welding 0.81 m2 @50								500.00
4	Hire charge for grinding machine								350.00
5	Transportation Charges for [illegible]								300.00
6	Providing synthetic enamel paint (P 105 It 15.60)								
	2X2.25X0.75X0.60 = 2.02						2.02	81.51	165.00
	Pipe								
	4.25X3.14X0.75 @ 10.08						10.08	81.51	822.00
II	Labour Charges								
a)	Welder Grader I (P XXXX II Sl. No. 33)						2.00	150.22	300.44
b)	Welder grader II						1.00	150.22	150.22
c)	Painter grader I						2.00	153.82	307.65
d)	Helper (Heavy)						1.00	149.58	149.58
							Total		5325.01
I	Over headed charges 10%								532.50
							Total		5857.51

Scanned with CamScanner

Sl. No	Description	Unit	No	Dimensions L	B	D	Qty	Rate	Amount
IV	Transportation charges (including Loading and Unloading)								
	Tractor Charges Rs 2374.40 per day (Page No XXXIII, It No. 20)								
	One Tractor Carries 40 Boards						Rs2374.40/40 Nos		59.36
								Total	5914.67
									591.47
V	Contractor profit 10%							Grand Total	6506.14
								Say	6506.00

(Rs. Six Thousand Five Hundred and Six Only for Each Board)

Executive Engineer.
Mukkal Division,
Bruhat Bangalore Mahanagara Palike

Herewith providing & supplying M.S. pipe name board including transportation charges. for Rs 6506-00. (Rs Six thousand five hundred & six only) for one board is approved.

Superintending Engineer (East)
Bruhat Bangalore Mahanagara Palike
BANGALORE

Scanned with CamScanner